GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

MA&UD Department - PH&MED – Kavali Water Supply Improvement Scheme with Sangam Anicut as source with an amount of Rs. 155.00 Crores – Administrative Sanction – Orders – Issued.

MAUNICIPAL ADMINISTRATION & URBAN DEVELOPMENT (UBS) DEPARTMENT

G.O.RT.No. 117 Dated: 14-02-2019

Read :

From the Engineer-in-Chief, Public Health, Guntur, Letter No. 1109 /T4/Nellore/Sangam anicut/WSIS/2018, dated 11-09-2018.

&&&&&

O R D E R:

In the reference read above, the Engineer-in-Chief, Public Health, Guntur has informed that Kavali is Grade – 1 Municipality located 14.920 North Longitude and 79.980 East Latitude and 8 Km from Bay of Bengal. The National Highway NH-5 is passing through the town. The area of Municipality is 60.09 Sq. Kms with a population of 97053 as per 2011 Census. Now the water is supplied to Kavali Municipality through Chinnakraka Reservoir which is feeding through canal from Sangam Reservoir of Penna River. The raw water is being drawn from Intake well located at Chinnakraka Reservoir to OHBR Located at hillock near Sangam. From this OHBR water is being pumped to SS tank of Capacity 2250 ML. At present, Kavali Municipality is having the water supply Infrastructure. Viz 1.Summer Storage Tank of 2250 ML 2.Water Treatment Plants 5.00, 5.77 MLD 3.OHBR – 250 KL and 4.ELSR's – 10 Nos of various capacities. In the entire 365 Days the Water from Canal coming from Sangam Reservoir is not sufficient causing the decreasing in water levels of Chinnakraka Reservoir especially during Summer period. He has informed that as per the instructions a Detailed Project Report with Sangam Anicut as source is prepared for an Amount of Rs. 155.00 Crores and submitted for according Administrative Sanction. The salient Features of the Project are as mentioned below:

1. Construction of Intake Well at Sangam Anicut
2. Providing Coffer dam and Approach Bridge to Intake Well.
3. Raw water pumping main from intake well to OHBR on Hillock.
4. Providing Pump sets and Transformer at Intake well.
5. Providing Pump sets and Transformer at Intake Well.
6. Construction of 704 KL GLBR on Hillock.
7. Provision towards SCADA and Statutory Charges.

(P.T.O.)

2. Government after careful examination of the matter hereby accord administrative sanction for an amount of Rs.155.00 crores for Kavali Water Supply Improvement Scheme with River Pennar as source from Sangam Anicut. The amount of Rs.155.00 crores shall be provided in the 2019-2020 Budget.

3. The Engineer-in-Chief, Public Health, Tadepalli shall take necessary further action in the matter.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

R.KARIKAL VALAVEN
PRINCIPAL SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief, Public Health, Tadepalli, Guntur
Sf/Sc

//FORWARDED BY ORDER//

RESEARCH OFFCER